



OFFICE OF
ENVIRONMENTAL
MANAGEMENT

ENERGY

Risk Summary

German Pebble Bed Research Reactor Highly Enriched Uranium (HEU) Fuel Project

Maxcine Maxted,
DOE-SR Used Nuclear Fuel Program Manager

July 8, 2014

Pre-Decisional DRAFT

Assumptions for Development of Risks

- Risks were developed based on current technology and approach
- Provided a High, Medium or Low ranking for probability
- Provided a Summary Consequence if the risk were realized
- Provided a timing for when the risk could be realized
- This is **NOT** a formal risk assessment. SRNS is working on a formal risk assessment now as part of the Work for Others (WFO).

Shipping Delays

Identified Risks

- b(5)
- Receipt of ships/railcars delayed
- Labor strikes/protests impact shipments
- Equipment is not available
- b(5)
- Potential Consequences
 - Operation Increased costs
 - Public perception issues

Medium Probability

Realization for most are after the contract is signed.
* realization would be before contract or addressed in contract

- Identified Risks
 - Railroad upgrades
 - Security upgrades for Storage Area
 - Pad costs under estimated
 - Unexpected Contents in Castor Cask *
- Potential Consequences
 - Increased costs
 - Schedule delays
 - Process upset *

b(5)

Low Probability

Realization for most are before the contract is signed.
* realization would be after the contract is signed

Carbon Digestion (Frame/equipment and scale up issues)

Identified Risks

- Pebble removal
- Material Accountability
- Off gas System Requirements
- Salt Accumulation in the offgas system
- Separation of Graphite, Uranium, Thorium, Fission Products and Salt

b(5)

Potential Consequences

- Increased costs
- Schedule delays
- Process upsets

High Probability (First of a kind Technology/Process)

b(5)

HEU Recovery and Down Blending

- Identified Risks
 - Material must be classified as Defense Material to utilize SRS facilities *
 - H-Canyon Operability (physical and budgetary concerns)
 - Security Requirements for kernel accumulation
- Potential Consequences
 - Show stopper (changes original approach) *
 - Increased costs
 - Increased blend materials for Thorium
 - Process upsets

b(5)

Medium Probability

Realization timing is varied from before contract to after.

High Level Waste Operations

- Identified Risks

- No tank capacity to support receipts
- Thorium in HLW system causes problems due to its Thixotropic nature
- HLW System Operability (physical and budgetary concerns)

- Potential Consequences

- Increased costs
- Schedule delays
- Process upsets

Medium Probability

Realization timing would be after contract finalization.

b(5)

Material /Waste Disposition

- Identified Risks

- Waste Incidental Reprocessing (WIR) determination *
- Number of glass canisters generated
- Location of appropriate disposal facilities (Waste Acceptance Criteria)
- Amount of waste generation

- Potential Consequences

- Show stopper (everything becomes HLW) *
- Increased costs
- Schedule delays
- Process upsets

b(5)

Medium Probability

Realization timing would be varied from before to after contract.

Summary

- Project stage is at a 0% design complete

- First of a kind technology

- b(5)

- b(5)

- b(5)

- We need to develop a contract that accounts for managing the risks even after the WFO work is completed.